

Proj arfios

to be used for the proposed project shown in the plans and detailed drawings.

- 4. All parts of the construction shall be finished with first class workmanship, to the fullest talent and meaning of the plans and these specifications, and to the entire satisfaction of the project inspector and the end-user.

- A. Mobilization/Demobilization

Provide the following:

- 1. Billboard with project information
- 2. Bunkhouse with office
- 3. Temporary comfort rooms
- 4. Site temporary enclosure may be blue sack or any suitable materials that may enclose the workplace.

- B. Demobilization includes cleaning up of site, clearing, hauling and disposal of waste and construction debris. Restoration of any damages shall also be done before exiting the area.

- 1. This work includes the dismantling of existing ceiling components inside the building and removal of existing boards inside the building.
- 2. Removal/retirement of existing electrical equipment needed to be replaced.
- 3. Removal of existing pin lights.
- 4. Strip work of old paints. Remove all chalky surface, loose paint, dirt and other contaminants by wire brushing or by using paint remover.
- 5. The area should - t

the

the apparent omission therein of detailed description or definition of the quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first class quality are t