

CAVITE STATE UNIVERSITY
D A C

BILL OF QUANTITIES

IMPROVEMENT OF SPORTS FACILITY PHASE II - 2nd Posting

ABC: 2,307,949.22

COLLEGE/UNIT/CAMPUS: MAIN CAMPUS

Bill of Quantities

Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	MOBILIZATION (Pesos _____ _____ and _____ centavos)				
II	DISMANTLING & CHIPPING WORKS (Pesos _____ _____ and _____ centavos)				
III	ELECTRICAL WORKS (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL					_____

Write grand total in words

Submitted by: _____ Date: _____
 Name of Bidder/Bidder's Representative: _____
 Position: _____
 Construction Company/Contractor: _____

SCOPE OF WORK:

A. IMPROVEMENT OF SPORTS FACILITY PHASE II

GENERAL NOTES:

1. The project should be finished in 60 calendar days.
2. Actual site inspection is a must.
3. This set of specifications shall govern the methods of construction and the kinds of materials to be used for the proposed project shown in the plans and detailed drawings.
4. All parts of the construction shall be finished with first class workmanship, to the fullest talent and meaning of the plans and these specifications, and to the entire satisfaction of the project inspector and the end-user.

B. Technical Description

I. Mobilization

A. Mobilization/Demobilization

Provide the following:

1. Billboard with project information
2. Bunkhouse with office
3. Temporary comfort rooms
4. Site temporary enclosure may be blue sack or any suitable materials that may enclose the workplace.

B. Demobilization includes cldrst

8. Include tapping to the source, electrical testing and commissioning.
 - a. Continuity test.
 - b. Insulation test.

9. Consult inspectors for details and extent of work.

Note: Electrical testing and guarantee, electrical supervision and final electrical inspection report should be signed and sealed by Electrical Engineer with notary public.

C. Contractor of the said project must provide an as-built plan of the project at the end of the contract as a requirement for the release of their final billing.

D. Contractor'