

Republic of the Philippines  
**CAVITE STATE UNIVERSITY**

Indang, Cavite

**BILL OF QUANTITIES**

**PROJECT: IMPROVEMENT OF ELECTRICAL POWER SYSTEM OF CEMDS  
NEW AND OLD BUILDING**

**Bill of Quantities**

**COLLEGE/UNIT/CAMPUS: CEMDS/MAIN CAMPUS**

## **CAVITE STATE UNIVERSITY**

### **SCOPE OF WORK:**

#### **A. IMPROVEMENT OF ELECTRICAL POWER SYSTEM OF CEMDS NEW AND OLD BUILDING**

##### **GENERAL NOTES:**

1. The project should be finished in 45 calendar days.
2. Site inspection is a must. Verify actual site condition.
3. This set of specifications shall govern the methods of construction and the kinds of materials to be used for the proposed project shown in the plans and detailed drawings.
4. All parts of the construction shall be finished with first class workmanship, to the fullest talent and meaning of the plans and these specifications, and to the entire satisfaction of the project inspector and the end-user.

#### **B. Technical Description**

##### **I. Mobilization**

###### **A. Mobilization/Demobilization**

Provide the following:

1. Billboard with project information
2. Bunkhouse with office
3. Temporary comfort rooms
4. Site temporary enclosure may be blue sack or any suitable materials that may enclose the workplace.
5. Demobilization includes cleaning up of site, clearing, hauling and disposal of waste and construction debris.
6. The area should be cleared/cleaned before and after construction work at least six meters away from the building line. Notify the end-user regarding the properties that need to be hauled away from the site prior to construction.

##### **II. EARTHWORKS**

